

REMEDIAL ROOF REFURBISHMENT NORTH SYDNEY

MAY 2019



Project Brief:

The client contacted VIKIN after many years of waterproofing failures and bandage solutions to an exposed concrete roof space.

Summary:

After inspection, it was confirmed that the existing failing fibre reinforced membrane be removed by grinding. Once done so, the cracks in the slab were treated and VIKIN Epoxy Primer / VIKINGuard Base / Hydraguard UV system was applied - bankrolling non slip aggregate so the space could accommodate foot traffic.

An insurance backed 15 year warranty was issued, but further to that VIKIN's / Macfin's expertise offered peace of mind and dry roof space after honest advice and diligent product performance advice practices.

Waterproofing Solutions Employed:

VIKIN Epoxy Primer
 VIKINGuard Base
 Hydraguard UV system



Before



After